

Post Secondary Institutions Strategic Infrastructure Fund (S.I.F.)

- Initiated in Spring 2016
- Mohawk College Total Project Value: \$54.25M

\$ 4.25 M Renovations to E-Wing

\$50.00 M New Building

\$20M Grant Received

mcCallumSather B+H



@NetZeroMohawk

Post Secondary Institutions Strategic Infrastructure Fund (S.I.F.)

Project Value: \$50M (\$47M Construction)

Estimated Building Size: 90,000 SF

Estimated Unit Cost: \$525/SF (rounded)





@NetZeroMohawk

JCPI Final Costing Detail

• Final Cost (Construction): \$47,610,000

• Final Area: 96,700 square feet


• Final Unit Cost: \$492/sq.ft.







@NetZeroMohawk

Building Type (Altus Group)	\$/Sq. Ft. – GTA (Altus Group)	
Universities & Colleges Teaching/Lecture Hall	395 - 520	
Universities & Colleges Laboratories (L1 & 2)	510 - 670	
Joyce Centre for Partnership and Innovation (Adjusted for Altus Cost Index of 1.04)	473	
ППОНАШК CCallumSather B+H	TIMP Concluding Engineers	@NetZeroMohawk



















Any project can be Net Zero

Provided you have enough \$\$\$



Or modest expectations for:

- Comfort
- Environmental Quality
- Amenities
- Etc.







Energy Targets – Design Meeting #1

75 ekWh/m²-yr (24.2 kBtu/ft²-yr)

CIEBUS College/University Average: 211 ekWh/m²-yr (68.1 kBtu/ft²-yr)

R10 window + wall

Ontario SB-10 Climate Zone 5 Requirement: R4.7





Energy Targets – Design Meeting #1

24.2 kBtu/ft²-yr

CIEBUS College/University Average: 68.1 kBtu/ft²-yr


R10 window + wall

Ontario SB-10 Climate Zone 5 Requirement: R4.7






	End Use	Radiant Heating / Cooling + GHSP	Radiant Heating / Cooling + GHSP + Solar Thermal		Water Source VRF + GHSP + Solar Thermal	Water Source VRF + Boiler / CT		
	Lighting	10.7			10.7			
D!	Misc. Equipment	19.3						
Design	Space Heating	17.1						
DC31811	Space Cooling	8.0					6.4	
	Pumps and Aux	9.6					4.8	
N/leeting # /	Fans	7.5					11.3	
Wiccuing mz	DHW	4.5					2.25	
·/-	Boiler	0.0					9.7	
"Engray	Total (ekWh/m²)	76.7						
LIICISY	Rank (lowest to highest)	5		3	2	7		
Design Meeting #2 "Energy Model"	Net Solar Thermal Effect (ekWh/m²)		-9.4	J	-4.9		-10.6	-
Model	Total ekWh	578.000	508,000	547.000	510.000	664.000	584,000	573.000
	Annual Energy Cost	\$ 69,360		- ,	,	,		
At 8,600 m ² and 5 storeys,	Size of PV Array (kWp)	525	462	497	464	604	53:	521
our roof area is estimated at	Size of PV Array (m²)	4,379	3,848	4,144	3,864	5,030	4,424	4,341
1,720m²	Flat Roof Area (m²)	8,758	7,697	8,288	7,727	10,061	8,848	8,682
	Cost of PV	\$ 1,320,000	\$ 1,160,000	\$ 1,250,000	\$ 1,160,000	\$ 1,510,000	\$ 1,330,000	\$ 1,310,000
	NREL Recommended O&M / year	\$ 9,900	\$ 8,700	\$ 9,375	\$ 8,700	\$ 11,325	\$ 9,975	\$ 9,825
	Linear m of Borehole	4,400	4,400	4,400	4,400			
	# of 500' boreholes	29	29	29	29			
RDH III ma	m ² Area of Field using 6 m spacing	1,039	1,039	1,039	1,039			
Making Buildings Better"	Cost of Borehole	\$ 440,000	\$ 440,000	\$ 440,000	\$ 440,000			










Water Cooled Geothermal VRF System


- Central geothermal condenser loop
- Heat recovery between heads on a circuit and between compressors
- Daikin VRF System











Heating Water System

- Entrance heat and remote terminal heat
- Backup for DHW solar thermal







RDH





™ тонашк

Central dedicated outdoor air system Local VAV boxes for demand based ventilation Carefully placed ventilation connection to fan coils Heat Recovery Wheel






















Solar Thermal

- Used to generate DHW and to augment condenser water loop heating
- Safeties for low load/no load conditions
- Viessmann panels, tanks and controls







CaGBC Zero Carbon Design Certification

- Embodied Carbon:
 - 482 kg CO2eq / m² (96 lb CO2eq/sqft)
- Operating Carbon:
 - -17.7 kg/m²-year (-3.5 lb CO2eq/sqft)








Performance Monitoring - Is It Working?



- Motivation
 - Living Lab
 - Course Integration








First Year of Operation


- September 15 2018 to September 15 2019
- Top floor not fully occupied
- · Whole building and PV generations reporting
 - Some weeks missing in the continuous monitoring
 - Check meters work just fine!
- Submetering challenges only a few months of data
- Calibrated energy model to be complete in early 2020
- · Have identified further operating savings
 - Lighting controls
 - Temperature setbacks











To Do: With a year of submeter data...

- Full Circle Energy Modelling
 - Weather
 - Schedules
 - Receptacle Loads
- Calibration (ASHRAE Guideline 14)
- Troubleshoot and Share





Changing the Culture













@NetZeroMohawk

Project Successes

Process:

Establishing the Energy Budget

Technology:

 Integrating proven technologies with innovative high performance building envelope

Impacts: Net Zero Targets Achievable

- · Net Zero Energy
- · Net Zero Carbon









@NetZeroMohawk

Project Challenges

- Commissioning Net Zero
- Metering Software
- Skilled Labour **Trades** Understanding & Awareness
- Staff Training
- Staff & Student Culture









@NetZeroMohawk

Thank you! **Questions?**

skemp@rdh.com tony.cupido@mohawkcollege.ca









Nohawk